



NOTES:

1. SIX (6) BUMPER BLOCKS SHALL BE REQUIRED FOR EACH SIGN INSTALLATION.
2. BUMPER BLOCKS SHALL BE PLACED AS DIRECTED BY THE ENGINEER, WITH RAPID SET EPOXY PER MANUFACTURER'S SPECIFICATION.
3. SEE DRAWING NO. 712 FOR SIGN INSTALLATION DETAILS.

COUNTY OF SONOMA  
 DEPARTMENT OF TRANSPORTATION  
 AND PUBLIC WORKS

BARRICADE PLACEMENT  
 FOR R1 SIGN INSTALLATION  
 IN PAINTED ISLAND

DATE: MAY 2004

REVISED: MAY 2018

APPROVED BY:

SCALE:

DRAWING NO.

JH

NONE

708